
CiB-9470 Installation


CiB-9470 Node (Front)
CiB-9470 Node (Back)
Unscrew 4 screws for take-out HBA Module- Screw 1
Unscrew 4 screws for take-out HBA Module- Screw 2

Unscrew 4 screws for take-out HBA Module- Screw 3 & 4 on site
Pull up HBA Module
Be careful pull up HBA Module, and let it on the site. **Please do not remove the cable connection (BLUE) **
Remove 3 cable connection

Unscrew 1 screw
Pull out boot drive Module (Image 1-2)
Pull out boot drive Module (Image 2-2)
Lift up the Air duct



Boot Drive Module Installation
Install the Boot drive module.
Boot Drive Module Installation
Boot Drive Module Installation
Connect 3 cables



Install Boot Drives then finish!